



PROFESSIONAL HOME INSPECTION

PROVIDING EXCEPTIONAL CLIENT SATISFACTION

■ HOME INSPECTIONS ■ RADON TESTING ■
■ TERMITES INSPECTIONS ■ WATER QUALITY ANALYSIS ■
■ WELL PERFORMANCE INSPECTIONS ■ MOLD

RADON TEST IN PROGRESS

TEST PERIOD = 48 HOURS

**PLEASE MAINTAIN CLOSED BUILDING CONDITIONS AS FOLLOWS FOR
THE DURATION OF THE TEST PERIOD**

1. Closed building conditions should begin 12 hours before the start of the test.
2. Closed building conditions need to be maintained throughout the duration of the test.
3. The test duration will be 48 to 96 hours.
4. All windows need to remain closed on each level of the building.
5. Doors should only be opened briefly for entry and exit of the building.
6. Internal-external air exchange systems such as whole house fans, window air conditioners set on fresh air (re-circulate setting only), and window fans should not be running.
7. HVAC - heating and central cooling systems may be operated as normal and as necessary.
8. Radon mitigation systems should be functioning 24 hours prior to and during the test period.
9. Equipment that brings outside air into the building may be operated only as necessary, such as combustion heating equipment, bathroom exhaust fans, clothes dryers and oven/range hoods.
10. Fireplaces, wood burning stoves or coal burning stoves may not be used or operated unless they are the only source of heat.
11. Do not run ceiling fans.